

OREGON CORNER RESTORATION FORM

Section 30 Township 1 N Range 37 E.

County Umatilla Date Sept., 1993

CORNER DESIGNATION

center 1/4, section 30
corner index; T-3

<input type="checkbox"/>	Condition Report Only
<input type="checkbox"/>	Not Found
<input type="checkbox"/>	Renewed
<input type="checkbox"/>	Unrecorded
<input checked="" type="checkbox"/>	Surveyed In
<input type="checkbox"/>	Referenced Out

Previous Renewals/Surveys, etc.


There is no previous recorded information regarding this corner.

Monument(s) & Accessories Found: (Condition and Source)

No evidence was found.

Monument Detail

Sketch



Monument Set (Procedures and Description)

At a section subdivision as determined by this survey I set a 3-1/4" aluminum cap on a 2-1/2"x 30" aluminum pipe, 26" in the ground, with a land survey monument sign attached to a steel post nearby.

New Accessories

- 9" douglas fir bears N.23-1/2°E., 17.5 feet scribed C1/4S30BT.
- 14" douglas fir bears N.66-1/2°W., 7.6 feet scribed C1/4S30BT.
- 16" douglas fir bears N.76°E., 7.1 feet scribed C1/4S30BT.
- 17" douglas fir bears S.40-1/2°W., 16.2 feet scribed C1/4S30BT.

I painted a 6" red band around all bearing trees and attached a bearing tree sign on the front with a land survey monument sign on the back. On the new bearing trees I attached a brass washer "PLS 2535" in the BT portion of the blaze.

Location & Comments

 RECEIVED BY _____
 Umatilla County Surveyor
 Date 12-93
 Rec'd By KR
 No. 93-93-B

Compass Declination 18° east
 Firm/Agency: White Shield, Inc
 Address: P.O. Box 477,
Grandview, WA 98930
 Party Chief: Dennis Hartmans
 Notes field bk. 3, pg. 17,18
 Witness Wes Cochran

Surveyor's Seal

