

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Timothy W. Davenport under GLO contract number 102, dated July 20, 1863. Surveyor General record states: Set qr Sec post from which;
A Red Fir 7 inch in dia bears N30°W 34 lks dist.
A Red Fir 5 inch in dia bears S60°W 18 lks dist.

The base line was resurveyed and reestablished by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states: Set a basalt stone 19x10x7 ins, 14 ins in the ground for ¼ sec cor marked BL ¼ on N face from which:

A cherry 3 in diam bears N30°E 15 lks dist marked ¼S BT
No other tree within limits and raised a mound of stone alongside.

The old ¼ sec cor, a badly decayed post bears W. 23.10 chs dist. I destroy this post and obliterate the marks on old bearing trees.


No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a stone 19x9x6 inches, laying on it's side with ¼ visible.

Found no evidence of the original Northeast bearing tree.

See map of survey dated September, 1989.



Description of monument and accessories I established to perpetuate the

original location of this corner: In place of the found original corner stone, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 22 inches in the ground, from which:

New Bearing objects:

A 3'x3'x3' high rock outcrop bears N59°E, 38.5 feet marked X B0 on center of Southerly face with a PK nail driven at the center of the cross.
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears N45°W, 6.93 feet.

Painted a 6 inch red band around the X B0 and attached bearing tree signs to both bearing objects.

Set a steel fencepost approximately 5 feet East with land survey monument sign attached.

Buried the original corner stone South and alongside of monument.

I hereby certify that the above corner point was perpetuated as hereon described on September 7, 1989.

Witnesses: Jeff Petersen and Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination.

Office of The Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office for record on the 27th day of October, 1989
David H. Krambia by Kathleen K. Amstutz
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Umatilla County Surveyor

*GPO-591-971, 1988

Date 10-89
Rec'd by KA
No. 89-101-B