

USDA-FOREST SERVICE

Index

File No.

J-3

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No.

Cor.

No.

T 1N R. 38E

R.D.

Walla Walla

County

Union

Merid. Willamette


N.F.

Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. F16616160 1577-

Filed At. Umatilla Nat For

Object Ident. Direct

Ident. By G. Langlitz

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Gary L. Langlitz

Signature

Land Surveyor

Title

Division PLS 1099

Division

Headquarters

Date 10-9-80

Date

7100-52 (3. 68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Corner set from survey at location determined by single proportionate measurement.

At the corner point, we set a 2"x30" galvanized iron pipe, 26" in the ground with brass cap attached, marked:

T1N R38E
S7
—+— ¼
S18
PLS 1099
1980

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

From which we mark new BT's.

A 22" Larch, scribed "¼ S7 BT" on a double blaze bears N73°W 84.8 ft.

And a 20" White Fir, scribed "¼ S18 BT" on a double blaze bears S53½°W 52.3 ft.

Attached brass washers stamped "LS 1099" to lower blaze of new BT's. Placed steel fencepost 5' East of monument with sign 54-9 attached. Attached signs and painted BT's per Standard Specifications For Cadastral Survey, U.S.F.S. Region 6, October 1979.

Work Done By. Gary Langlitz Title Land Surveyor Date 10-9-80 State Registration No. PLS 1099
or Agency

Certified Cor. Record Prepared? Yes No Filed At: Union County Surveyor Date Dec. 1980

REMARKS

Compass Declination: 18° East

Witness: Mike Wagoner