


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 17
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on September 29, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 22" x 8" x 8", for the corner to sections 2 and 3, at the intersection of the base line 6 chains and 68 links west of the mound for the corner to sections 33 and 34, T. 1 N., R. 29 E.



Original corner evidence recovered:

Found the original corner stone solidly set 12 inches in the ground. The corner stone is 23" x 10" x 10" and is plainly marked with two notches on the east edge and "CC" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the east side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N33° 30' E, 79.4 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S2", attached at ground level, bears S29° 30' E, 77.8 feet.


A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 S3", attached at ground level, bears S47° W, 71.3 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N48° 30' W, 95.6 feet.

I hereby certify this corner point was perpetuated as hereon described on October 24, 2002.

Magnetic declination set in compass: 20° E.

NAD '83 UTM Zone 11 position: 5042624N 329153E (plus or minus two meters)



Dennis L. Gaylord

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 11-02
 Rec'd By KK
 No. 02-270-R