

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 5  
DIAGRAM

**History of original corner establishment:**

The original corner was established by George S. Pershin, deputy, (compassman) on November 7, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 24" x 7" x 5", for the corner to sections 5 and 6, at the intersection of the base line 6 chains and 53 links west of the corner to Township 1 N., Ranges 29 and 30 E.

T1N R29E  
S36  
S6|S5  
T1S | R30E  
C C  
PLS 1636  
2002

**Original corner evidence recovered:**

Found the original corner stone solidly set on the east edge of a mound of stones, protruding 7 inches above the ground. The corner stone is 24" x 8" x 7" and is plainly marked with five notches on the east edge and "CC" on the south face.

**Monument and accessories established to perpetuate the original position of this corner:**

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 25" into the ground. I bury several pieces of iron at the base of the monument as a memorial. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the north side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 33" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N66° E, 137.0 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 S5", attached at ground level, bears S72° E, 120.2 feet.

A 5/8" x 24" iron rod set 36" into the ground, in an agricultural field, with a 3/4" brass washer, marked "PLS 1636 S6", attached at the top, bears S37° W, 91.0 feet.

A 5/8" x 36" iron rod set 33" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N53° W, 158.2 feet.

I attach a "Witness Post" sign to a steel fence post 3.5 feet west of the corner.

I hereby certify this corner point was perpetuated as hereon described on October 25, 2002. Magnetic declination set in compass: 12° E (Base line is visible to the east for about 2 miles). NAD '83 UTM Zone 11 position: 5042458N 334047E (plus or minus two meters)

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Dennis L. Gaylord*  
DENNIS L. GAYLORD  
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 11-02  
Rec'd By AK  
No. 02-268-R