

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

V - 19
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on October 27, 1871, under joint GLO contract No. 154, as follows:

T1S R30E
1/4 S26
S35
PLS 1636
2002

Set a stone, 18" x 8" x 5", for 1/4 section corner.

Original corner evidence recovered:

Found the original corner stone loosely set in a mound of stones. Corner stone is 18" x 10" x 4" and is plainly marked "1/4" on one face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 27" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and build a mound of stones around the pipe, from which:

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N62° E, 183.8 feet.

A 5/8" x 24" iron rod set 22" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S46° E, 167.5 feet.

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S47° W, 174.6 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N43° W, 138.2 feet.

I nailed a "Witness Post" sign to a wooden fence post one foot east of the corner.

I hereby certify the above corner point was perpetuated as hereon described on March 3, 2002. Magnetic declination set in compass: 18° E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Dennis L. Gaylord
OREGON
JULY 14, 1978
DENNIS L. GAYLORD
1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
Umatilla County Surveyor
Date 6-02
Rec'd By KR
No. 02-1444