


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

X - 9
DIAGRAM



History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on November 2, 1871, under joint GLO contract No. 154, as follows:

Set a stone, 18" x 6" x 5", for 1/4 section corner.
Va: 19° 08' E

Original corner evidence recovered:

Found the original corner stone solidly set and protruding 8" out of the ground. The corner stone is on the west edge of a mound of three stones. The corner stone is 20" x 9" x 6" and is plainly marked "1/4" on the west face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 24" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the south side of the pipe and place the original mound around the pipe, from which:

A 5/8" x 24" iron rod set 23" into the ground with a 3/4" brass washer, marked "PLS 1636 NE", attached at ground level, bears N37° 30' E, 77.2 feet.

A 5/8" x 36" iron rod set 34" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S27° E, 115.0 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S28° 30' W, 119.1 feet.

A 5/8" x 24" iron rod set 21" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N42° W, 112.9 feet.

I hereby certify the above corner point was perpetuated as hereon described on March 10, 2003.

Magnetic declination set in compass: 21° E.

NAD '83 UTM Zone 11 position: 5033608N 335405E (plus or minus two meters)


REGISTERED PROFESSIONAL LAND SURVEYOR
 OREGON
 JULY 14, 1978
DENNIS L. GAYLORD
 1636

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY
 Umatilla County Surveyor
 Date 5-03
 Rec'd By KK
 No. 03-70-R