

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla

DATE: 3/4/94

CORNER DESIGNATION: Z-13. S.E. Corner Section 33, T1S., R30E., W.M..

PREVIOUS RENEWALS/SURVEYS, ETC.: The original survey was made by George Williams and George S. Pershin under contract No.154, dated June 6th, 1871. Original notes state a 18 X 8 X 6 stone was set for the Section Corner. Section corner location was noted with reference to the foot of a basalt ledge to the West, and to a road to the East.

MONUMENT & ACCESSORIES FOUND: There is an existing East-West fence passing through the corner area and the area has been farmed on both sides of the fence. There is no evidence of the original corner stone. After thorough investigation and tying the existing road and the basalt ledge it is apparent that the road is in the same location that it was when the original survey was performed. The corner position was re-established holding the East-West fence line for latitude, between original topographic calls to the center of the road and the foot of basalt ledge. The present measurements between the foot of basalt ledge and center of road match the original record within 1 foot.

**MONUMENT DETAIL:**

T1S	R30E
S33	S34
S4	S3
T2S	R30E
1994	
PLS 1106	

MONUMENT SET: Set a 2 1/2" brass cap on a 1 1/4" X 30" galvanized iron pipe, 29" in the ground, with a mound of earth to the cap.

**New Accessories:**

A brass washer stamped "PLS 1106" nailed to railroad tie fence corner post East of County Road, bears S 87° E, 98.8 feet.  
 A brass washer stamped "PLS 1106" nailed to railroad tie fence corner post West of County Road, bears S 84° E, 36.5 feet.  
 A brass washer stamped "PLS 1106" nailed to power pole, bears S 31° E, 75.6 feet.  
 A brass washer stamped "PLS 1106" nailed to rail road tie corner post Southwest of house, bears N 65° W, 169.4 feet.  
 Brass washers are approximately 1 foot above the ground level and have a bearing object sign nailed above them.

**LOCATION AND COMMENTS:**

COMPASS DECLINATION: 18° East  
 FIRM/AGENCY: William R. Wells, PLS  
 P.O. Box 1696  
 Pendleton, Oregon 97801

Party Chief: Robert D. English  
 Notes: Robert D. English  
 Witness: F. Scot Munro

Surveyor's Seal

REGISTERED PROFESSIONAL LAND SURVEYOR
---

*W. R. Wells*

OREGON JULY 22, 1977 WILLIAM R. WELLS 1106
---

*renews 12-31-94*

RECEIVED BY  
 Umatilla County Surveyor  
 Date 7-94  
 Read By KK  
 No. 94-82-B