


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Z - 3  
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, Deputy, on October 24, 1871, under GLO contract No. 154, as follows:

Set a stone, 20" x 8" x 4", on top of a hill for the 1/4 section corner to sections 31 and 6.



Original corner evidence recovered:

Found the original corner stone solidly set on the northwest edge of a mound of stones. The corner stone is 20" x 10" x 4" and is plainly marked "1/4" on the south face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 18" flared, galvanized iron pipe 17" into the ground to bedrock. I bury the corner stone along the northwest side of the pipe and build a mound of stones around the pipe. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above, from which:

- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NE", wired to the rod at ground level, bears N23° E, 114.8 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SE", wired to the rod at ground level, bears S46° 30' E, 114.7 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 SW", wired to the rod at ground level, bears S25° W, 123.1 feet.
- A 5/8" x 24" iron rod, set 23" into the ground, with a 3/4" brass washer, marked "PLS 1636 NW", wired to the rod at ground level, bears N44° W, 77.2 feet.

I hereby certify the above corner point was perpetuated as hereon described on February 11, 2004. Magnetic declination set in compass: 17° E.  
NAD '83 UTM Zone 11 position: 5032876N, 332926E (plus or minus two meters).

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dennis L. Gaylord*

OREGON  
JULY 14, 1978  
DENNIS L. GAYLORD  
1836

Renews June 30, 2005

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY  
Umatilla County Surveyor  
Date 2-04-  
Rec'd By KK  
No. 04-33-R