

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A - 7
DIAGRAM

History of original corner establishment:

The original corner was established by George S. Pershin, deputy, (compassman) on October 24, 1871, under joint GLO contract No. 154, as follows:

T1S R30E
1/4 S32
S5
T2S
PLS 1636
2003

Set a stone, 20" x 8" x 4", in a canyon for 1/4 section corner to sections 5 and 32, T. 1 & 2 S., R. 30 E.

Original corner evidence recovered:

Found the original corner stone solidly set and protruding 4" from the ground. The corner stone is 20" x 9" x 6" and is marked "1/4" on the north face.

Monument and accessories established to perpetuate the original position of this corner:

In place of the original corner stone, I set a 1" x 30" flared, galvanized iron pipe 28" into the ground. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I bury the corner stone along the west side of the pipe and build a mound of stones around the pipe, from which:

A railroad tie fence corner post with a 3/4" brass washer, marked "PLS 1636 NE", nailed to the tie at a point one foot above the ground, bears N65° E, 56.3 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SE", attached at ground level, bears S35° E, 99.6 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 SW", attached at ground level, bears S48° W, 108.0 feet.

A 5/8" x 36" iron rod set 35" into the ground with a 3/4" brass washer, marked "PLS 1636 NW", attached at ground level, bears N48° 30' W, 102.4 feet.

I fasten a "witness post" sign to a steel fence post 1.4 feet east of the corner.

The corner is 53 feet east of the center of a draw (record is 2 chains). The references to the west of the corner are west of the draw.

I hereby certify this corner point was perpetuated as hereon described on February 22, 2003.

Magnetic declination set in compass: 18° E.

NAD '83 UTM Zone 11 position: 5032817N 334565E (plus or minus two meters)



Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on:

RECEIVED BY

Umatilla County Surveyor

Date 5-03

Rec'd By [Signature]

No. 03-66-R