

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 9/07/95

CORNER DESIGNATION: G-17. East 1/4 corner Section 10, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by James P. Currin and James E. Noland, under Special Contract, dated May 4, 1887.

Surveyor General records state:  
Set post, 3 ft. long, 3 ins. sq., 24 ins. in ground, for 1/4 Sec. Cor., marked 1/4 S. on W. face, from which,  
A fir, 6 ins. diam., brs. N. 30° E., 5 lks. dist., marked 1/4 S., B.T.  
A fir, 6 ins. diam., brs. S. 25° W., 46 lks. dist. marked 1/4 S., B.T.

MONUMENT AND ACCESSORIES FOUND: An 18 in. diameter fir stump with previously opened blaze scribed "4S" inside 6 in. of overgrowth, bears S 25° W, 30.4 feet (46 lks) per record. No trace of original wood post was recovered. Found a 1 1/2" diameter 33 in. long iron pipe lying on the ground in vicinity of re-established corner position.

**MONUMENT MARKING DETAIL:**

T1S R34E  
1/4  
S10 ! S11  
1995  
ORLS 1639

MONUMENT SET: At the position established by the reversed record bearing and distance (N 25° E., 46 lks - 30.4 feet) from the recovered record Section 10 bearing tree set a 2 1/2" brass cap on a 1 1/2 in. x 30 in. galvanized iron pipe, projecting 6 in. with a 2 foot diameter mound of stone (marked as shown in the monument detail).

From which:

A 6 in. ponderosa pine with double blaze scribed "1/4 S10 BT" bears N 21° W., 35.8 feet.  
An 8 in. douglas fir with double blaze scribed "1/4 S11 BT" bears S 24° W, 8.6 feet.  
A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1639" bears N 35° E, 13.5 feet.  
A 5/8" x 30" iron rod with yellow plastic cap marked "OR PLS 1639" bears N 89° W, 8.7 feet.  
A 1/2" brass washer stamped "PLS 1639" was nailed to lower blaze of each bearing tree.  
Attached bearing object signs to each iron pin, set steel fence post near corner monument with witness sign attached.

LOCATION & COMMENTS: Corner falls on East facing hillside approximately 50 feet West of abandoned Rail Creek Road and approximately 150 feet South of a ravine.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Witness: William L. Hanley, PLS  
Rod Lewis, LSIT



RECEIVED BY  
Umatilla County Surveyor  
Date 10-95  
Rec'd By KK  
No. 95-170-B