

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 9/07/95

CORNER DESIGNATION: J-17. Southeast corner Section 10, T1S., R34E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by James P. Currin and James Noland, under Special Contract dated May 4, 1887.

Surveyor General records state:
Set basalt stone, 12 x 8 x 6 ins., 8 ins. in the ground, for Cor. to Secs., 10, 11, 14 & 15, marked 4 notches on S., 2 notches on E. edges. Raised mound of stone around it, pits impracticable.

MONUMENT AND ACCESSORIES FOUND: A firmly set basalt stone 13 in. x 8 in. x 7 in. with 3 distinct grooves on 1 face and 2 faint grooves on another face, with a surrounding mound of stone.

MONUMENT MARKING DETAIL:

T1S R34E
S10 | S11

S15 | S14
1995
ORLS 1639

MONUMENT SET: At position of found basalt stone set a 2 1/2 in. brass cap on a 1 1/2 in. x 30 in. galvanized iron pipe, projecting 6 in. with a 3 foot diameter mound of stone to cap (marked as shown in the monument detail). Original stone was buried on West side of new monument.

New Accessories:

A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1639" bears N 62° E, 11.9 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1639" bears S 15° E, 19.1 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1639" bears S 59° W, 29.1 feet.
A 5/8" x 30" iron pin with yellow plastic cap stamped "OR PLS 1639" bears N 17° W, 19.2 feet.
Attached bearing object sign to each iron pin and set steel fence post near corner monument with witness sign attached.

LOCATION & COMMENTS:

Corner falls on steep West facing hillside in a clearing approximately 200 feet below top of ridge and approximately midway between two East-West running ravines.

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

Party Chief: William L. Hanley, PLS
Witness: Rod Lewis, LSIT



RECEIVED BY
Umatilla County Surveyor
Date 10-95
Rec'd by KK
No. 95-170-B