

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 09/26/08.

CORNER DESIGNATION: J-19, The South One-Quarter Corner of Section 11, Township 1 South, Range 34 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally established by James P. Currin and James E. Noland under their Special Contract dated May 4th, 1887. Notes state: Set basalt stone 10 x 8 x 8 ins. for 1/4 Sec. Cor. marked 1/4 on North face and raised a mound of stone around it.

MONUMENT AND ACCESSORIES FOUND: In June of 2007, I visited this corner in the company of Mr. Bob Burns and found a 3 1/2 foot stone mound with a 10" by 8" by 8" basalt stone in the center of it. There was a old unreadable "K" tag on a 18" ponderosa pine tree located South 44° East, 9.1 feet from the stone mound. I did not observe marks on the rough basalt corner stone but accepted it as the corner point. Earlier this summer a new fence was built North and approximately West from the corner, and the fence builders picked up all the surface stones and placed them in rock jacks. We were able to recover the hole where the original corner stone and mound stood, as well as below ground portions of the stone mound and remonumented the corner point as indicated.

MONUMENT MARKING DETAIL:

T1S R34E
1/4 S11
S14
2008
PLS 1106

MONUMENT SET: At the center of the original mound of stone, set a 2 3/8" brass cap on 1 1/4" x 22" galvanized iron pipe 14" in the ground to bedrock, and surrounded with a mound of earth and stone. Cap is marked as shown in "Monument Marking Detail".

New accessories:

- A 12" ponderosa pine scribed "1/4S11BT" on single blaze bears North 48° West, 37.8 feet.
 - A 6" ponderosa pine scribed "X" at breast height and "BT" at base bears North 07° East, 121.3 feet.
 - A 18" ponderosa pine scribed "1/4S11BT" on single blaze bears North 50° East, 82.3 feet.
 - A 17" ponderosa pine scribed "1/4S14BT" on single blaze bears South 44° East, 9.1 feet. There is a old "K" tag on this bearing tree.
- Attached bearing tree signs to all bearing trees. Attached witness sign to gate post for fence extending West, a few feet South of the corner.

LOCATION AND COMMENTS: Corner is located in gate opening with new fences West and North.

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT

\1S34J19

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-2010

RECEIVED BY

Umatilla County Surveyor

Date 10-08

Rec'd By KK

No. 08-131-R