

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 7/28/94

CORNER DESIGNATION: Z-11. South 1/4 corner Section 33, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set post 3 ft. long, 3 ins. square, 24 ins. in the ground in exact place of old cor. for 1/4 sec. cor. marked S.C. 1/4 S on N. face, from which: A Black Pine, 12 ins. in diam. (old B.T.) bears N.3°E. 28 lks dist., marked 1/4 S.S.C.B.T. A Black Pine, 16 ins. in diam. (old B.T.) bears S.25°E. 27 lks. dist., marked 1/4 S.S.C.B.T." Reference to original corner from survey made by Timothy Davenport, under Contract No. 102, dated July 20, 1863. Re-monumented by Umatilla County Surveyor in 1967.

MONUMENT AND ACCESSORIES FOUND: Found 2 1/2" brass cap on a 1 1/4" galvanized iron pipe, protruding 7" out of the ground.

Bearing Trees:

A 14" lodge pole pine stump bears N 46° E-17.0 feet, visible scribing: BT, (1967 bearing tree).

A 16" lodge pole pine bears S 58° W-10.2 feet, visible scribing: S 1/4 S33 T1N R35, (1967 bearing tree).

MONUMENT MARKING DETAIL:

UMATILLA COUNTY

SURVEYOR

S33

1/4 -----

S4

1967

MONUMENT SET:

New Accessories:

Set steel fence post 2.3 feet North of monument with witness sign attached.

An 11" spruce bears S 63° E-25.2 feet, scribed: 1/4 S4 SC BT.

A 12" spruce bears N 37 1/2° W-40.9 feet, scribed: 1/4 S33 SC BT.

An 8" lodge pole pine bears N 03° W-14.7 feet, scribed: 1/4 S33 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

LOCATION & COMMENTS:

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680600.06

E = 8728596.50

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS

P.O. Box 1696

Pendleton, Oregon 97801

Party Chief: Robert D. English

Notes: Robert D. English

Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY

Umatilla County Surveyor

Date 2-95

Rec'd By KL

No. 95-116-C