

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/5/94

CORNER DESIGNATION: Z-15. South 1/4 corner Section 34, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone 16 x 12 x 9 ins., 10 ins. in the ground at exact place of old cor. for 1/4 sec. cor., marked S.C. 1/4 on N. face, from which: A Pine, 12 ins. in diam. (old B.T.) bears S.20°E 45 lks. dist., marked S.C.1/4 S.B.T. A Pine, 10 ins. in diam. bears N.26°E. 54 lks. dist., marked S.C.1/4 S.B.T. The other old bearing tree has been cut down."

Reference to old corner and accessories are from original survey record by Timothy Davenport, Contract No. 102, dated July 20, 1863.

MONUMENT AND ACCESSORIES FOUND: None. Corner re-established by single proportionate measurement between the recovered Southwest corner of Section 34 and the recovered Southeast corner of Section 34.

MONUMENT MARKING DETAIL:

T1N R35E
S34
1/4 -----
S3
T1S R35E
1994
PLS 1106

MONUMENT SET:

At position determined by survey set a 2 1/2" brass cap on 1 1/4" x 12" flared galvanized iron pipe, 16" in the ground to solid basalt, (cap marked as shown in monument detail). Corner falls in pavement.

New Accessories:

A 6" lodge pole pine bears N 78° W-125.1 feet, scribed: 1/4 34 SC BT.

A 7" lodge pole pine bears N 05° E-149.0 feet, scribed: 1/4 S34 SC BT.

A brass washer by electrical junction box, at northwest corner of gravel shed bears S 64° E-119.5 feet.

A brass washer at the base of power pole #035900, Umatilla Rural Electric Association, bears S 12° W-136.3 feet.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red. Attached bearing object and witness signs near brass washers.

LOCATION & COMMENTS: Corner falls in centerline of intersection of Highway 30 and Horseshoe Ridge Road at the state gravel sheds.

STATE PLANE CO-ORDINATE:

Oregon North Zone, NAD 83/91, U.S. Survey Foot:

N = 680726.20
E = 8733890.69

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801
Party Chief: Robert D. English
Notes: Robert D. English
Witness: F. Scot Munro

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Renews 6/30/96

RECEIVED BY
Umatilla County Surveyor
Date 2-95
Rec'd By KK
95-116-C