


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

111  
H-176  
5

A-1

History of original corner establishment: Corner established in 1881 by Jacob C. Cooper, under General Land Office Contract No. 397



Surveyor General Records (notes) states:

Set a post 4½ ft. long, 4 in. square, 24 in. in the ground in heavy timber for the closing Cor to T1S, R35 & 36E, marked T1S on the south, R36E, S6 on the East, R35 S1 on the north faces, with 6 notches on the south east and west faces.

A fir 16 in. diam. bears S24°W 1/4 1ks dist. marked T1S, R35E S1 BT.

A tamarack 10 in. diam. bears S74°E 24 lks dist. marked T1S, R36E S6 BT.

(No subsequent remonumentations indicated in county records)

**Description of corner evidence found:**

Found a 18 in. tamarack with all scribing visible bearing S74°E 15.8 ft. dist. from the corner position.

Found a 40 in. fir down and rotten with reversed scribing clearly visible bearing S 24°W 27.0 ft. dist. from the corner position.

**Description of monument and accessories established to perpetuate the original location of this corner**

Set a 30 in. x 2½ in. iron pipe marked as shown, 24 in. in the ground, for the closing corner to Sec. 1 & 6.

From which new BT's


A fir 14 in. diam. bears N36°E 43 ft. dist. marked T1N, R36E S21 BT.

A fir 8 in. diam. bears S32E 16.2 ft. dist. marked T1S R36E S6CC BT.

A spruce 14 in. diam. bears S24°W 49.5 ft. dist. marked T1S R35E S1 CC BT.

Distances taken to a brass washer in the blaze of each tree.

Set a steel fence post approximately 5 ft. east from corner with Forest Boundary sign attached.



Used steel tape and magnetic compass with declination = 20° E.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Douglas M. Ferguson*  
OREGON  
JULY 12, 1928  
DOUGLAS M. FERGUSON  
848

Office of Seaside County of Clatsop  
State of Oregon, I hereby certify that the within instrument was filed in this office

for record on the 14th day of August, 1972 at 10 o'clock a.m. (signed)

*Douglas M. Ferguson* by \_\_\_\_\_  
(COUNTY OFFICIAL) (DEPUTY)