

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla DATE: 9/6/94

CORNER DESIGNATION: Z-7. South 1/4 corner Section 32, T1N., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Most recent approved GLO Survey was made by James P. Currin and James Noland, under Special Contract dated May 4, 1887. Notes state: "Set basalt stone 9 x 8 x 7 ins., 6 ins. in the ground for 1/4 sec. cor. (in exact spot of old cor.) marked S.C. 1/4 on N. face, from which: A Red Fir (old bearing tree) 12 ins. in diam. bears S5°E. 74 lks dist., marked S.C. 1/4 S.B.T. A Red Fir (old bearing tree) 16 ins. in diam. bears S 70°W 65 lks. dist., marked S.C. 1/4 S.B.T. Reference to original markings from survey made by Timothy Davenport, under Contract No. 102, dated July 20, 1863."

MONUMENT AND ACCESSORIES FOUND: Found original stone, clearly marked, lying East of corner mound, obviously displaced by logging operation.

**MONUMENT MARKING DETAIL:**

1/4 T1N R35E  
S32  
-----  
S5  
T1S R35E  
1994  
PLS 1106

**MONUMENT SET:**

At the center of found stone mound, set 2 1/2" brass cap on a 1 1/4" x 30" galvanized iron pipe, 22" in the ground, with stone in mound South of monument, (marked as shown in monument detail).

**New Accessories:**

Set steel fence post 3.5 feet North of monument with witness sign attached.

A 15" ponderosa pine bears N 39° E-48.8 feet, scribed: 1/4 S32 SC BT.

A 12" douglas fir bears N 57° W-11.6 feet, scribed: 1/4 S32 SC BT.

A 16" ponderosa pine bears S 74° E-56.2 feet, scribed: 1/4 S5 SC BT.

A 19" douglas fir bears S 15° E-20.5 feet, scribed: 1/4 S5 SC BT.

Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached bearing object and witness signs to each tree, painted a 6" band and face of blaze red.

**LOCATION & COMMENTS:**

**STATE PLANE CO-ORDINATE:**

Oregon North Zone, NAD 83/91, U.S. Survey Foot:  
N = 680461.63  
E = 8723312.02

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS  
P.O. Box 1696  
Pendleton, Oregon 97801

Party Chief: Robert D. English  
Notes: Robert D. English  
Witness: F. Scot Munro

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6/30/96*

RECEIVED BY

Umatilla County Surveyor  
Date 2-95  
Rec'd By KK  
No. 95-16-C