

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 12/27/95
CORNER DESIGNATION: C-13. East 1/4 corner Section 4, T1S., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by Thompson & Chaplin under Contract #104 dated April 16, 1864.

Surveyor General records state:

Set post for 1/4 Sec. Cor., from which,

A pine, 12 ins. diam., brs. S.40°E., 76 lks. dist.

A pine, 12 ins. diam., brs. N.10°W., 45 lks. dist.

Corner remonumented by by Currin & Noland under Special Contract dated May 4, 1887. Surveyor General records state:

I found the 1/4 Sec. Cor., which I found to be a post, 36 x 3 x 3 ins., marked 1/4 S. on W. face, rotted off at top of ground, from which,

A pine, 12 ins. diam., brs. S.40°E., 76 lks. dist., marked 1/4 S., B.T. and the stump of a pine, 10 ins. diam., brs. N.10°W., 45 lks., marked 1/4 S., B.T.

I set new post, 36 x 3 x 3 ins., 24 ins. in ground, marked 1/4 S. on W. face and marked

A pine, 5 ins. diam., brs. S.45°W., 4 lks. dist., 1/4 S.B.T.

MONUMENT AND ACCESSORIES FOUND: A basalt stone 10" x 9" x 7" basalt stone marked "X" flush with the ground at fence intersection North and West. This stone shown on Survey No. 83-140-C.

A 10" diameter stump 28" high scribed "BT" with chaining notch below which bears N 10° W, 29.7 feet (45 lks, per Thompson & Chaplin 1864 record and Currin and Noland 1887 record).

MONUMENT MARKING DETAIL:

T1S R35E

1/4

S4-|-S3

1995

ORLS 1639

MONUMENT SET:

I removed the original corner stone and in its place set:

A 1 1/2" diameter by 30" long galvanized iron pipe with a 2 1/2" brass cap, projecting 2" out of the ground marked as shown in monument marking detail. Corner stone buried alongside monument. Monument has a 6' steel fence post alongside with witness sign attached.

A 7" diameter lodgepole pine bears N 80° E, 31.1 feet, scribed "1/4 S3 BT" on double blaze.

A 16" diameter lodgepole pine bears S 32° E, 133.2 feet, scribed "1/4 S3 BT" on double blaze.

A 5" diameter lodgepole pine bears N 84° W, 4.6 feet, scribed "X" at breast height and "BT" below.

A 12" diameter lodgepole pine bears N 29° W, 81.2 feet, scribed "1/4 S4 BT" on double blaze.

Each new bearing tree has a Umatilla County bearing tree sign attached above the upper blaze and a brass washer marked PLS 1639 nailed to the face of the lower blaze, with face of blazes painted red.

Original bearing tree stump has a Umatilla County bearing object tag attached above the blaze, with face of blaze painted red.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East

FIRM/AGENCY: William R. Wells, PLS

P.O. Box 1696

Pendleton, Oregon 97801

Witness: William Hanley, PLS 1639

Dawn Tubbs

Surveyor's Seal

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

RENEWS 06/30/97

RECEIVED BY

Umatilla County Surveyor

Date 95-221-B

By KK

No 12-95