


History of original corner establishment:

This corner was originally set by Currin & Nolin under special contract dated May 1887.

The original notes state that at the corner a 3 foot long 3 inch square post was set 24 inches in the ground from which:

A 24" pine bears N5°E 15LK marked 1/4 SBT.

A 5" tamarack bears N70°W 40LKS marked 1/4 SBT.



Description of corner evidence found:

Found 24" ± diameter pine stump with visable scribing "BT" on slab next to stump.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2" X 30" iron pipe with 2 1/2" brass cap S5°W-9.9 feet from found bearing tree stump.

Established 2 new bearing trees:

A 14" western larch bears N54°E - 35.6 feet scribed 1/4 S4BT.


A 12" western larch bears N83°W - 62.2 feet scribed 1/4 S5BT.

Monument is buried 20" in ground and surrounded with a mound of earth. Used staff compass with 20° east declination and measured to center of bearing trees.

Corner was set June 4, 1983.

Witness: Stanley G. Wallulis

CAP IS MARKED:



REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of Sunnyvale County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 22nd day of February 1985
 by Betty Cochran
 (COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd By _____
 No. 85-12-A