

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/10/95

CORNER DESIGNATION: L-9. West 1/4 corner Section 16, T1S., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by U.S. Deputy Surveyors Currin & Noland under Special Contract dated May 4, 1887. The Surveyor General records state: Set post, 3 ft. long by 4 ins. sq. 24 ins. in ground for 1/4 Sec. Cor., marked 1/4 S. on W. face; raised a mound of stone alongside. Pits impracticable.

Corner was recovered and remonumented in 1974, Survey No. J-77.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a 2" by 36" galvanized iron pipe, marked as shown in Monument Marking Detail. The monument was found lying flat on the ground just West of a stone mound.

MONUMENT MARKING DETAIL:

1/4
17|16
1974
RLS 933

MONUMENT SET:

Re-established corner position by distance-distance measurement from the Southwest corner of Sec. 16 and C-W 1/16th corner monuments using record distances from Survey No. J-77. The re-established corner position fits the location of the existing down monument and stone mound.

At re-established corner position, set a 5/8" x 30" iron pin with yellow plastic cap marked "OR PLS 1106 WA PLS 17372". Buried old monument horizontally South of new monument. The iron pin monument was set because of shallow rock conditions.

New Accessories:

An 10" ponderosa pine bears N 41° E, 21.5 feet, scribed "1/4 S16 BT".
A 10" douglas fir bears S 20° E, 12.5 feet, scribed "1/4 S16 BT".
A 6" maple bears S 52 1/2° W, 53.2 feet, bark scribed "1/4 S17 BT".
An 8" lodgepole pine bears N 47 1/2° W, 43.7 feet, scribed "1/4 S17 BT".
Set steel fence post 2 feet Southeast of corner with witness sign attached.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Party Chief: William R. Wells, PLS
Notes: Rodney Lewis, LSIT

William R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-96

RECEIVED BY
Umatilla County Surveyor
Date 10-95
Rec'd By KK
No. 95-168-B