

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N - 5  
DIAGRAM

**History of original corner establishment:**

The original corner was established by James P. Currin and James E. Noland on July 1, 1887, under their special contract, as follows:

T1S R35E  
S18|S17  
S19|S20  
PLS 1636  
2001

Set a post, 48" x 4" x 4", 2 feet into the ground for the corner to sections 17, 18, 19 and 20, properly marked, from which:

- A 20" fir bears N45°E, 15 links (9.9 feet).
- A 10" fir bears S20°E, 15 links (9.9 feet).
- A 4" pine bears S60°W, 46 links (30.36 feet).
- A 5" pine bears N63°W, 62 links (40.92 feet).

**Corner evidence recovered:**

- A live and vigorous 30" Douglas-fir with a single healed blaze bears N45°E, 9.90 feet.
- A 13" Lodgepole Pine snag with scribing visible on a nearly healed blaze bears S72°W, 30.36 feet.

**Monument and accessories established to perpetuate the original position of this corner:**

At record distance from the two recovered original bearing trees, and record bearing from the original bearing tree to the northeast, I set a 1" x 30" flared, galvanized iron pipe 13" into the ground to bedrock. A 2 1/2" brass cap attached to the top of the pipe is marked as shown in the diagram above. I build a mound of stone around the pipe, from which:

- A 9" Western Larch, scribed "T1S R35E S20 BT", bears S21° 30'E, 42.4 feet.
- A 13" Douglas-fir, scribed "T1S R35E S19 BT", bears S52° 30'W, 46.7 feet.
- A 19" White Fir, scribed "T1S R35E S18 BT", bears N35°W, 18.2 feet.

The new bearing trees are scribed on double blazes and have a 3/4" brass washer, marked "PLS 1636", nailed flush to the bottom of the lower blaze.

I hereby certify the above corner point was perpetuated as hereon described on September 7, 2001. Magnetic declination set in compass: 18°E.

  
*Dennis L. Gaylord*

Renews June 30, 2003

Recorded at the office of County Surveyor, County of Umatilla, State of Oregon, on \_\_\_\_\_, 2001

RECEIVED BY  
 Umatilla County Surveyor  
 Date 10-01  
 Rec'd By KK  
 No. 01-169-R