

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 8/10/95

CORNER DESIGNATION: N-9. Southwest corner Section 16, T1S., R35E., W.M.

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by U.S. Deputy Surveyors Currin & Noland under Special Contract dated May 4, 1887. The Surveyor General records state:

Set post, 4 ft. long by 4 ins. sq. 24 ins. in ground for Cor. to Secs. 16, 17, 20 & 21, marked,

T.1 S., R.35 E., S.16 on N.E.

S.17 on N.W.

S.20 on S.W.

S.21 on S.E. faces, and

3 notches on S. and

4 notches on E. edges, from which,

A fir, 8 ins. diam., brs. N.45°E., 27 lks. dist., marked T.1 S., S.16 B.T.

A pine, 24 ins. diam., brs. S.30°E., 35 lks. dist., marked T.1S., R.35E., S.21, B.T.

A pine, 20 ins. diam., brs. S.70°W., 34 lks. dist., marked T1S., R.35 E., S.20, B.T.

A fir 4 ins. diam., brs N.40°W., 29 lks dist., marked T.1S., R.35E., S17, B.T.

Corner was recovered and remonumented in 1974, Survey No. J-77.

MONUMENT AND ACCESSORIES FOUND: Found a 2 1/2" brass cap on a 2" galvanized iron pipe, protruding 10" from the ground, cap is unstamped.

From which:

A root hole bears S 30° E, 23.1 feet.

A rotted ponderosa pine stump bears S 70° W, 22.5 feet, no remaining scribing.

MONUMENT MARKING DETAIL:

S17|S16

S20|S21

1995

PLS 1106

Note: Cap is rotated to N 40° W

MONUMENT SET:

Added the marks shown in Monument Marking Detail to existing monument.

New Accessories:

An 8" white fir bears N 17 1/2° E, 48.7 feet, scribed "T1S R35E S16 BT".

A 6" iron spike with brass washer in center of 34" sawn white fir stump bears S 59° E, 7.4 feet. Washer is marked "PLS 1106".

A 9" ponderosa pine bears S 09 1/2° W, 95.4 feet, scribed "T1S R35E S20 BT".

An 11" western larch bears N 57° W, 64.0 feet, scribed "T1S R35E S17 BT".

Set steel fence post 2 feet North of corner with witness sign attached.

LOCATION & COMMENTS:

COMPASS DECLINATION: 18° East.

Surveyor's Seal

FIRM/AGENCY: William R. Wells, PLS
P.O. Box 1696
Pendleton, Oregon 97801

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Party Chief: William R. Wells, PLS
Notes: Rodney Lewis, LSIT

RECEIVED BY
Umatilla County Surveyor

Date 10-95

Rec'd By KK

No. 95-168-B

Will R. Wells
OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 6-30-96