


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner originally established by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states: Set a basalt stone 14x12x4 ins 9 ins in the ground for closing cor of secs 2 + 3 marked CC with 2 notches on E and 4 notches on W edges from which:  
 A pine 20 ins diam bears S20°E 144 lks dist mkd T1S R36E S2 CC BT  
 A pine 24 ins diam bears S20°W 30 lks dist mkd T1S R36E S3 CC BT  
 No other trees within limits and raised a mound of stone alongside



Corner perpetuated by Lawrence D. Holmes under BLM group no. 1184 with instructions dated Sept. 29, 1983. His notes state: Point for closing cor of secs 2 and 3, at proportionate distance; there is no remaining evidence of the original corner. Set an iron post, 28 ins. long, 2½ ins diam, 24 ins in the ground in a collar of stone, 2½ ft base to top, with brass cap marked: (markings shown below) from which:  
 A ponderosa pine, 18 ins diam, bears S7 3/4°E, 49 lks dist mkd T1S R36E S2 CC BT  
 A ponderosa pine, 15 ins diam, bears S33 3/4°W, 164 lks dist mkd T1S R36E S3 CC BT

No record of subsequent monumentation found in Umatilla County survey records.

**Description of corner evidence found:**

Found a standard BLM brass cap monument marked as shown:

**BLM BEARING TREES**

Found a 14 inch diameter Ponderosa Pine S7 3/4°E, 49 lks, dead and standing with scribes visible.

Found a 16 inch diameter Ponderosa Pine S33 3/4°W, 164 lks, live and vigorous with scribes visible.

Found steel fenceposts approximately 5 feet South and West with Property Boundary signs and a Land Survey Monument sign on the Southerly post.

Bearing and distance to the BLM bearing trees is as per the BLM notes. I find no obvious errors.

See map of survey dated September, 1989.


**Description of monument and accessories | established to perpetuate the**

**original location of this corner:** From the found BLM corner monument:

**New Bearing Tree:**

A 18 inch diameter Ponderosa Pine bears S80°E, 11.04 feet marked T1S R36E S2 CC BT

Painted a 6 inch red band around all Bearing Trees and attached Bearing Tree and Land Survey monument signs.



I hereby certify that the above corner point was perpetuated as hereon described on August 10, 1989.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 21° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept. County of Umatilla  
 State of OR I hereby certify that the within instrument was filed in this office  
 for record on the 27 day of October 1989  
Duane I. Griffith by Kathleen K. Amober  
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

\*GPO-591-971, 1988

Umatilla County Surveyor  
 Date 10-89  
 By KA  
 No. 89-101-B