


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states:
Intersect the base line 21.14 chs E. of cor to Secs 35 & 36 T1N R36E; Set a basalt stone 14x10x6 ins 9 ins in the ground for closing cor to Secs 1 and 2 marked CC with 1 notch on E and 5 notches on W edges from which:

A pine 36 ins diam bears N20°W 125 lks dist marked T1N R36E S36 BT
No other tree within limits and raised a mound of stone alongside.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument or it's accessory.

See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the original location of this corner: At position determined by survey, I set a 2½" x 30" aluminum pipe with aluminum cap marked as shown, 26 inches in the ground, from which:

New Bearing Objects:

A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears S80°E, 6.84 feet
A 5/8"x30" iron pin with plastic cap marked BGA SURVEY MARKER bears S12°W, 11.42 feet

Raised a mound of stone around monument, 3 ft. base to top of cap.

Attached bearing tree signs to the bearing objects.


Set a steel fence post approximately 5 feet West with Land Survey Monument and Property Boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on September 14, 1989.

Witnesses: Jeff Petersen and Rick Robinson.



Signature of Duane I. Griffith



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination.

Office of the Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 27 day of October, 1989
David H. Kumbier by Kathleen Kumbier
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-89

Initials KA

No. 89-101-B

*GPO-591-971, 1988