


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states:

Set a basalt stone 12x9x5 ins 8 ins in the ground for ¼ sec cor marked ¼ on W face, from which;
 pine 20 ins diam bears N50°W 112 lks dist marked ¼S BT
 No other tree within limits and raised a mound of stone alongside
 Corner remonumented in 1972 by Douglas M. Ferguson, OPLS 848. His record states:
 Found 26 in pine live in good condition with scribing visible.
 Established corner position S50°E 74 ft distance from BT.
 Set 30 in x 2½ in iron pipe with 3 in brass cap marked as shown
 26 in in the ground and raised a mound of stone around the pipe for the ¼ corner between Sec 1 and 2 from which a new BT- A fir 16 in diam bears S12°E 11.4 ft dist marked T1S R36E S1 BT. Distance taken to a brass washer in the base of the BT. Set a steel fencepost approximately 5 ft. North from corner.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found a 3" brass cap monument marked as shown:

ORIGINAL BEARING TREE


Found a 28 inch diameter Ponderosa Pine N50°W, 112 lks, live but sickly with scribes visible.

FERGUSON BEARING TREE

Found a 21 inch diameter Douglas Fir S12°E, 11.4 feet, live and vigorous with blaze evident.

Distances to the BTs are to the estimated face of blaze.

See map of survey dated September, 1989.



Description of monument and accessories established to perpetuate the original location of this corner: From the above described corner monument:

New Bearing Tree:

A 12 inch diameter Douglas Fir bears N83°W, 10.05 feet marked ¼ S2 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with Property Boundary and Land Survey Monument signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 7, 1989.

Witnesses: Jeff Petersen and Rick Robinson

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Duane I. Griffith
OREGON
JULY 10, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept. County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 27 day of October 1989
David H. Kumbstein by Kathleen K. Amberg
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 10-89
 Rec'd by KA
 No. 89-101-B

*GPO-591-971, 1988