

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment: Corner established in 1882 by Herman D. Graton under General Land Office Contract No. 452.

Surveyor General Records (notes) states:

Set a basalt stone 12 x 9 x 5 ins. 8 ins. in the ground for 1/4 Sec. Cor. marked 1/4 on W face, from which

A pine 20 ins. diam. bears N50°W 112 lks. dist. marked 1/4 S BT.

No other tree within limits and raised a mound of stone alongside.



C-2

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 26 in. pine live in good condition with scribing visible, established corner position S50°E 74 ft. distance from BT.


Description of monument and accessories established to perpetuate the original location of this corner

Set 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown 26 in. in the ground and raised a mound of stone around the pipe for the 1/4 corner between Sec. 1 and 2, from which a new BT -

A fir 16 in. diam. bears S12°E 11.4 ft. dist. marked TIS R36E 1/4 S1 BT.

Distance taken to a brass washer in the blaze of the BT.

Set a steel fence post approximately 5 ft. North from corner with Forest Boundary sign attached.



Used steel tape and magnetic compass with declination = 20° East.



Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that this within instrument was filed in this office  
 for record on the 14th day of April, 1972 at 11 o'clock a.m., (signed)  
Douglas M. Ferguson by \_\_\_\_\_ (DEPUTY)  
 (COUNTY OFFICIAL)