


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.
See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 24 inches in the ground, from which:

New Bearing Trees:

- A 13 inch diameter White Fir bears S82°E, 37.23 feet marked C 1/4 S1 BT
- A 14 inch diameter Western Larch bears S1°W, 12.16 feet marked C 1/4 S1 BT

- Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.
- Set a steel fence post approximately 5 feet East with Land Survey Monument and Property Boundary signs attached.
- Raised a mound of stone around monument, 3 ft. base to top of cap.

I hereby certify that the above corner point was perpetuated as hereon described on September 10, 1989.



REGISTERED PROFESSIONAL LAND SURVEYOR

Duane I. Griffith
OREGON
JULY 19, 1964
DUANE I. GRIFFITH
644

I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 27th day of October, 1989
David H. Krumbein by Kathleen K. Amstutz
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor
Date 10-89
By KA
No. 89-101-B

*GPO-591-971, 1988