


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Herman D. Gradon under GLO contract number 452, dated June 16, 1882. Surveyor General record states: Set a post for the cor to secs 1, 2, 11 + 12 from which; A fir 5 in diam bears N70°E 17 lks dist marked T1S R36E S1 BT A fir 7 in diam bears S20°E 19 lks dist marked T1S R36E S12 BT A tamarack 6 in diam bears S15°W 27 lks dist marked T1S R36E S11 BT. A fir 10 in diam bears N30°W 90 lks dist marked T1S R36E S2 BT Corner remonumented in 1972 by Douglas M. Ferguson, OPLS 848. His record states: Found 12 in tamarack with scribing visible S15°W 17.8 ft. Found 24 in fir, down and rotten with scribing visible N30°W 59.5 ft. Set a 30 in x 2½ in iron pipe with brass cap marked as shown (markings shown below) from which; A fir 20 in diam bears N60°E 50.3 ft marked T1S R36E S1 BT. A spruce 12 in diam bears S12°E 42.3 ft marked T1S R36E S12 BT. A tamarack 18 in diam bears N53°W 25.2 ft. marked T1S R36E S2 BT. Corner perpetuated by Lawrence D. Holmes under BLM group no. 1184 with instructions dated Sept. 29, 1983. His notes state: Cor of secs 1,2,11,12 monumented with an iron post marked: (markings shown below) from which the original bearing trees: A larch snag 12 in diam bears S13°W 27 lks with scribe marks. A down fir 24 in diam bears N30°W 90 lks no marks visible. The remains of Ferguson BTs: A sawn fir stump bears N50°E 76 lks no marks visible. A larch 18 in diam bears N56°W 38 lks with healed blaze. New BTs: A spruce 15 in diam bears



Description of corner evidence found:

Found a 3 inch brass cap monument marked as shown:

N89 3/4°E 51 lks dist mkd T1S R36E S1 BT. A Fir 9 in diam bears S28¼°E 86 lks dist mkd T1S R36E S12 BT. A spruce 14 in diam bears S54¼°W 44½ lks dist mkd T1S R36E S11 BT. No record of subsequent monumentation found in Umatilla County survey records.

ORIGINAL BEARING TREE

Found an 11" Western Larch S15°W, 27 lks dead and standing with scribes visible. Found the decayed remains of a large White Fir N30°W, 90 lks, no marks visible (BT painted on remaining bark).

FERGUSON BEARING TREES

Found a 12" Spruce S12°E, 42.3 ft. dead and down with scribes
Found a 20" Western Larch N53°W, 25.2 feet live and vigorous with scribes visible.

BLM BEARING TREES

Found a 16" Spruce N89 3/4°E, 51 lks live & vigorous with scribes
Found a 10" White Fir S28¼°E, 86 lks live & vigorous with scribes
Found a 17" Spruce S54¼°W, 44½ lks live and vigorous with scribes
NOTE: Bearings and distances given are as per the individual record. I find no obvious errors. See map of survey dated 9-89.


Description of monument and accessories I established to perpetuate the original location of this corner:

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Also found a steel fencepost approximately 5 feet Northwesterly with Attention sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 3, 1989.

Witnesses: Jeff Petersen and Rick Robinson



Office of Office Survey Dept County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 27th day of October, 1989
Duane I. Griffith by Kathleen K. Amosberg
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

*GPO-591-971, 1988

10-89
 KA
 No. 89-101-B