


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Herman D. Gradon, under General Land Office Contract No. 452.



Survey General Records (notes) states:

Set a post 4 ft. long 4 ins. square 2 1/4 ins. in ground for the Cor. to Sec. 1, 2, 11, & 12. Marked T1S, S1 on NE, R36E S12 on SE S11 on SW and S2 on NW faces, with 5 notches on S & 1 notch on E edge from which

A fir 5 ins. diam. bears N70°E 17 lks. dist. marked T1S R36E S1 BT.

A fir 7 ins. diam. bears S20°E 19 lks. dist. marked T1S R36E S12 BT

A tamarack 6 ins. diam. bears S15°W 27 lks. dist. marked T1S R36E S11 BT

A fir 10 ins. diam. bears N30°W 90 lks. dist. marked T1S, R36E S2 BT.

E-21

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 12 in. tamarack live in good condition with scribing visible bearing S15°W 17.3 ft. dist. from the corner position.

Found a 24 in. fir, down and rotten, with reverse scribing clearly visible bearing N30°W 59.5 ft. dist. from the corner position.

Description of monument and accessories established to perpetuate the original location of this corner


Set a 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap, marked as shown, 25 in. in the ground for the corner to Sec. 1, 2, 11, and 12, from which new bearing trees -

A fir 20 in. diam. bears N60°E 50.3 ft. dist. marked T1S R36E-S1 BT.

A spruce 12 in. diam. bears S12°E 42.3 ft. dist. marked T1S R36E S12 BT.

A tamarack 18 in. diam. bears N53°W 25.2 ft. dist. marked T1S R36E S2 BT.

Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. north of corner with "Attention" sign attached.



REGISTERED PROFESSIONAL LAND SURVEYOR

OREGON JULY 12, 1966 DOUGLAS M. FERGUSON 848

Used steel tape and magnetic compass with declination = 20° East.

Office of Sherburn County of Clatsop State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 14th day of April, 1972, at 10 o'clock am, (signed) Douglas M. Ferguson (COUNTY OFFICIAL) by _____ (DEPUTY)