


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Corner not previously established.



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Corner not previously established.

See map of survey dated September, 1989.

Description of monument and accessories I established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Trees:


- A 12 inch diameter Western Larch bears S28°W, 17.70 feet marked W 1/16 S12 BT
- A 8 inch diameter Western Larch bears N36°W, 24.12 feet marked W 1/16 S1 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument and property boundary signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 18, 1989.

Witness: Jeff Petersen



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept. County of Umatilla  
State of OR I hereby certify that the within instrument was filed in this office for record on the 27<sup>th</sup> day of October 1989  
David A. Krumbein by Patricia K. Ambrose  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY  
Date 10-89  
Initials KA  
No. 89-101-B

\*GPO-591-971, 1988