


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

E-25

**History of original corner establishment:**

Corner was originally established by Jacob C. Cooper under GLO Contract No. 397, dated July 1, 1881. Surveyor General records state:  
 A fir 5 ins diam which I marked for cor to secs 1, 6, 7 and 12, T1S S6 on NE, R37 S7 on SE, R36 S12 on SW and S1 on the NW faces with 5 notches on the S and 1 notch on the N edges, from which; A pine 7 ins diam bears S80°E 7 lks dist marked T1S R37E S7 BT. A pine 4 ins diam bears N45°E 5 lks dist marked T1S R37E S6 BT. A pine 12 ins diam bears S66°W 15 lks dist marked T1S R36E S12 BT. A pine 12 ins diam bears N19°W 21 lks dist marked T1S R36E S1 BT.  
 See sheet 2 for additional history records.



**Description of corner evidence found:**

Found a 20" white fir corner tree, from which:  
 A 2½" aluminum cap on a 2½" aluminum pipe reference monument protruding 1" out of ground, marked as shown in corner diagram, bears North, 4.0 feet.  
 An 18" white fir stump, uprooted, bears N 83° E (m/l) - 12 feet, healed blaze.  
 A 22" white fir stump, uprooted, bears S 25° W (m/l) - 23 feet, healed blaze.  
 A 12" dead lodge pole pine bears N 20° W - 14.2 feet, visible scribing, 13.8 feet to face.

**Description of monument and accessories established to perpetuate the original location of this corner:**

5.0' North of corner tree set steel fence post with 54-2 and 54-9 signs attached, 1.0 feet North of reference monument.  
 A 5/8" x 30" iron pin with yellow plastic cap bears N 58° W - 20.7 feet.  
 A 5/8" x 30" iron pin with yellow plastic cap bears S 17° W - 17.8 feet.  
 A 5/8" x 30" iron pin with yellow plastic cap bears S 65° W - 27.5 feet.  
 All iron pins have 54-3 signs attached and steel fence posts near with 54-9 sign attached. Bearings and distances to corner.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards by me on August 2, 1994.

Compass declination 18° East.

Sheet 1 of 2 (continued on page 2)

REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

*Will. R. Wells*

OREGON  
 JULY 22, 1977  
 WILLIAM R. WELLS  
 1106

*renews 12-31-94*

Office of Surveyor County of Umatilla  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 7 day of December, 1994  
David H. Klein by \_\_\_\_\_  
 (COUNTY OFFICIAL)

RECEIVED BY

Umatilla County Surveyor  
 Date 12-94  
 Rec'd By XK  
 No. 94-120-B

