


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established by Jacob C. Cooper in 1831 under General Land Office Contract No. 397.

Surveyor General Records (Notes) states:

A fir 5 in. diam. on table land in dense timber which I marked for corner to Sections 1, 6, 7 & 12; TIS S6 on NE - R37E S7 on SE - R36E, S12 on SW faces with 5 notches on the S and 1 notch on the N edges from which:

- A pine 7 in. diam. bears S80°E 7 lks. dist. marked TIS, R37E S7 BT.
  - A pine 4 in. diam. bears N45°E 5 lks. dist. marked TIS R37E S6 BT.
  - A pine 12 in. diam. bears S66°W 15 lks. dist. marked TIS R36E S12 BT.
  - A pine 10 in. diam. bears N19°W 21 lks. dist. marked TIS R36E S1 BT.
- Corners in TIS R37E were set in subsequent resurvey.



E 25

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found 18 in. fir, original corner tree, with healed over blaze visible on 4 sides, from which:

Found a rotten lodge pole pine, no scribing visible, bearing S80°E, 5 ft. from corner tree.

Found a 6 in. lodge pole pine, dead and down, with scribing visible, bearing approximately N45°E 3. ft. from corner tree.

Found a 1 1/4 in. lodge pole pine, dead and down, with scribing visible, bearing approximately S66°W 10 ft. from corner tree.

Found a 1 1/4 in. lodge pole pine, live in good condition, bearing N19°W 14 ft. from corner tree.

Description of monument and accessories established to perpetuate the original location of this corner

No brass cap monument set. Original corner tree is in good condition. Took new bearing trees:

A fir 1 1/2 in. diam. bears N80°E 12 ft. dist. marked TIS R37E S6 BT.

A fir 20 in. diam. bears S32°W 22.5 ft. dist. marked TIS R36E S12 BT.


Distances taken to a brass washer in the blaze of each tree.

Set a steel fence post approximately 5 ft. South from corner position with Forest Boundary sign attached.

Used steel tape and magnetic compass with declination = 20° East.

REGISTERED PROFESSIONAL LAND SURVEYOR

*Douglas M. Ferguson*  
OREGON  
JULY 12, 1968  
DOUGLAS M. FERGUSON  
848



Office of Surveyor County of Hamilton  
 State of Oregon, I hereby certify that the within instrument was filed in this office  
 for record on the 15th day of October, 1972, at 10 o'clock am, (signed)  
Douglas M. Ferguson by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)