


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established by Jacob C. Cooper in 1881 under General Land Office Contract No. 397.



Surveyor General Records (Notes) states)
 Set post $4\frac{1}{2}$ ft. long 4 in. square, 2 ft. in the ground with rd. of stone around $3\frac{1}{2}$ ft. at base 18 in. high, on the NE side of head of ravine, 1600 ft. above creek near open timber for Cor. to Secs 7, 12, 13, & 18 marked: T1S, S7 on NE, R37E, S18 on SE, R36E, S13 on SW and S12 on the NW face with 4 notches on the S and 2 notches on the N. edge from which:
 A pine 28 in. diam. bears S27W 66 lks. dist. marked T1S, R36E S13 BT.
 Subsequent resurvey placed set of corners for T1S R 37E.

5-25

(No subsequent remonumentations in county records)


Description of corner evidence found:

Found a mound of stone with remains of original post in ground, from which a pine, 36 in. diam. live in good condition, with scribing visible, bears S 27°W 37 ft. distance. Apparently the original surveyor was in error as the record is 43.5 ft dist.
 Accepted remains of old post as the corner position.

Description of monument and accessories established to perpetuate the original location of this corner

Set 30 in. x $2\frac{1}{2}$ in. iron pipe with 3 in. brass cap marked as shown, 25 in. in the ground and raised a mound of stone around the pipe for the Cor. to Sections 12 & 13, from which new BT's--
 A pine $1\frac{1}{4}$ in. diam. bears S78°E 48.3 ft. marked T1S R37E S7 BT.
 A pine 12 in. diam. bears N34°W 79.5 ft. marked T1S R36E S12 BT.
 Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. East from corner with "Attention" sign attached.

Used steel tape and magnetic compass with declination = 20° East.



REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

Douglas M. Ferguson
 OREGON
 JULY 12, 1973
 DOUGLAS M. FERGUSON
 848

Office of *Sherman* County of *Wasco*
 State of *Oregon*, I hereby certify that the within instrument was filed in this office for record on the *13* day of *August*, 19 *73*, at *10* o'clock *am*, (signed)
Douglas M. Ferguson by _____ (DEPUTY)