


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1882 by Herman D. Graddon, under General Land Office Contract # 452. Surveyor General Records (notes) states: Set a basalt stone 14x14x8 ins, 9 ins. in ground for the Cor. to Sec. 15, 16, 21, & 22, marked with 3 notches on S and E edges. From which

- A pine 8 ins. dia. bears N 15° E 290 lks. dist. marked T1S, R36E S15 BT
- A pine 22 ins. dia. bears S 25° E 194 lks. dist. marked T1S, R36E S22 BT
- A fir 30 ins. dia. bears S 25° W 120 lks. dist. marked T1S, R36E S21 BT
- A fir 14 ins. dia. bears N 65° W 145 lks. dist. marked T1S, R36E S16 BT



17

(No subsequent remonumentations in county records)


Description of corner evidence found:
 Found a 30" pine, alive in good condition, with scribing visible. Established corner position N 25° W 128 ft. dist. from tree.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 30"x2 1/2" iron pipe with 3" brass cap marked as shown, 25" in the ground and raised a mound of stone around the pipe for the corner to section 16, 15, 21 & 22, from which new BT's

- A 16" pine bears N 2° E 311.8 ft. dist. marked T1S, R36E S15 BT
- A 14" fir bears S 35° W 72.0 ft. dist. marked T1S, R36E S21 BT
- A 14" fir bears N 52° W 84.3 ft. dist. marked T1S, R36E S16 BT

Distances taken to a Brass washer in the blaze of each tree.
 Set a steel post approximately 5' north of corner with Attention sign attached.



Used steel tape and magnetic compass with declination-- 20° E



Office of Sherman County of Washtenaw
 State of Michigan, I hereby certify that the within instrument was filed in this office for record on the 14th day of April, 1977; at 10 o'clock am, (signed)
Ralph W. Ferguson by _____
 (COUNTY OFFICIAL) (DEPUTY)