


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established this survey.



Description of corner evidence found:

NONE

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2" brass cap on a 2" iron pipe 6" above the ground in earth and rock mound with a 6" steel fence post alongside with signs 54-4 and 54-3 attached.

New bearing trees:

A fir 7" diam bears N 42° E., 12.4 ft dist marked S1/16 S 21 BT
A fir 10" diam bears S 14°30' W., 4.5 ft dist marked S 1/16 S 20 BT

Each BT has a sign 54-3 attached 6" below a band of red paint and has a brass washer marked RPE 2808 nailed flush with BT blaze.

Brass cap is marked:

T 1 S R 36 E
S1/16

S 20 S 21

R P E 2 8 0 8
1976



Office of.....Surveyor..... County of.....Umatilla.....
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)