


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Jacob C. Cooper, under General Land Office Contract No. 397.



Surveyor General Records (notes) states:

Set post 4 ft. long 4 ins. square, 24 ins. in the ground on the North slope of hill, 100 ft. below the summit in heavy timber, for Cor to Secs. 19, 24, 25, & 30, marked T1S, S19 on NE, R36E S30 on SE, R35E S25 on SW and S24 on the NW faces, with 2 notches on the S and 4 notches on the N edges.

- A fir 18 ins. diam. bears S81°W 23 lks. dist. marked T1S R35E S25 BT.
- A tamarack 16 in. diam. bears S49°E 25 lks. dist. marked T1S R36E S30 BT.
- A tamarack 14 in. diam. bears N47°E 25 lks. dist. marked T1S R36E S19 BT.
- A fir 16 in. diam. bears N58°W 19 lks. dist. marked T1S R35E S24 BT.

R-1

A subsequent survey placed a set of corners for T1S, R35E.
(No subsequent remonumentations in county records)

Description of corner evidence found:

Found a 20 in. fir stump rotted off at ground level with faint scribing visible, bearing S81°W 15.2 ft. dist. from corner position.

Found the rotten remains of a tamarack with scribing visible, bearing S49°E 16.5 ft. dist. from the corner position.

Found the rotten remains of a tamarack, bearing N47°E 16.5 ft. dist. from the corner position.


Found a rotten fir stump, bearing N58°W 9.9 ft. dist. from the corner position.

Description of monument and accessories established to perpetuate the

original location of this corner Set a 30 in. x 2 1/2 in. iron pipe with 3 in. brass cap marked as shown, 28 in. in the ground for the Corner to Sections 19, 20, and 24, from which new BT's-

- A tamarack 10 in. diam. bears N17°E 12.8 ft. dist. marked T1S R36E S19 BT.
- A lodge pole pine 10 in. diam. bears S42°E 12.7 ft. dist. marked T1S R36E S30 BT.
- A ponderosa pine 12 in. diam. bears S10°W 13.6 ft. dist. marked T1S R35E S24 BT.

All distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. East from Corner with "Attention" sign attached.



Used steel tape and magnetic compass with declination = 20° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1909
DOUGLAS M. FERGUSON
848

Office of Surveyor County of Washouille
State of Oregon, I hereby certify that the within Instrument was filed in this office for record on the 14th day of Nov, 1972, at 11 o'clock a.m. (signed)
Douglas M. Ferguson by _____ (DEPUTY)
(COUNTY OFFICIAL)