

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-147

33
15

History of original corner establishment: Corner established in 1881 by Jacob C. Cooper under General Land Office Contract No. 397.

Surveyor General Records (notes) states:

Set post 4 ft. long, 4 in. sq. 24 in. in ground on the West slope in dead and fallen timber, 300 ft. below the summit for the Cor to Secs. 19, 24, 25, and 30, marked T1S S19 on NE, R37E S30 on SE, R36E S25 on SW and S24 on the NW face with 2 notches on the South and 4 notches on the North edge from which:

- A pine 40 in. diam. bears N80°W 61 lks. dist. marked T1S R36E S24 BT.
- A pine 36 in. diam. bears S40°W 188 lks. dist. marked T1S R36E S25 BT.
- A pine 32 in. diam. bears S3°E 60 lks. dist. marked T1S R37E S30 BT.

Subsequent survey placed a set of corners for T1S R37E.

(No subsequent remonumentations in county records)

Description of corner evidence found:

Found a 40 in. pine, live in good condition, with all scribing visible, bearing N80°W, 40.3 ft. dist. from the corner position.

Found a 32" pine down and rotter, blaze and ax marks visible with scribing burnt out. Bearing S3°E 39.5 ft. from the corner position.

Found a 36 in. pine snag (dead) with all scribing visible. Bearing S40°W 71.2 ft. from corner position.

Notes give 188 lks. distance; original surveyor apparently intended to give 108 lks. distance.

Compass bearing South intersects corner to Sec. 19 & 30, T1S, R37E.

Description of monument and accessories established to perpetuate the original location of this corner


Set a 30 in. x 2½ in. iron pipe with 3 in. brass cap marked as shown, 24 in. in the ground for the corner to Sec. 24 & 25, T1S R 36E, from which new BT's--

A fir 14 in. diam. bears S56°E, 4.8 ft. dist. marked T1S R37E S19 BT.

A tamarack 16 in. diam. bears S76°W 12.6 ft. dist. marked T1S R36E S25 BT.

Distances taken to a brass washer in the blaze of each tree. Set a steel fence post approximately 5 ft. North from corner position with "Attention" sign attached.

Used steel tape and magnetic compass with declination = 20° East.




R-25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson

OREGON
JULY 12, 1908
DOUGLAS M. FERGUSON
848



Office of Surveyor County of Wasco
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 15 day of Nov, 1972, at 11 o'clock am, (signed)
Ralph W. Anderson by _____ (DEPUTY)
(COUNTY OFFICIAL)

H-147