

USDA-FOREST SERVICE

Index

File No.

R-6

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No.

Cor.

No.

T 1S

R.

36E

R.D.

Pendleton

County

Umatilla

Merid. Willamette


N.F.

Umatilla

State

Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

2 1/2" Gal. steel pipe with a 2 1/2" Brass cap properly stamped and firmly set in a mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

RPE 2808 12" Fir now a 12" D-Fir S13W-16.5 ft. scribing visible on partially healed blaze.  
 RPE 2808 6" Fir now a 6"x6' tall snag N20E-57ft. scribing visible on unhealed blaze.  
 Guard post South with signs 54-2 and 54-9.

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From its junction with Rd. #3102 follow spur 020 one mile to posted N/S line corner is about 150 ft. North in creek bottom.

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_  
*Agency*

Signature

*Larry D. Busing*

Title

Land Surveyor

Division

Headquarters

Date

10/82

7100-52-(3.68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

11" Wh.Fir N2OE, 78.3 ft. scribed W1/16S20BT  
and with a 1" Brass disk stamped PLS 896.

Work Done By Larry D. Bishop Title Surveyor Date 10/82 State Registration No. 896  
or Agency

Certified Cor. Record Prepared ? Yes No  Filed At: \_\_\_\_\_ Date \_\_\_\_\_

REMARKS

Exchanged 54-9 for 54-4 signs on existing BT's.  
Nailed 54-9 and BT signs to new BT and painted band and blaze red.

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

12

13

Index R-6  
File No. \_\_\_\_\_CORNER RECORD (SEARCH)  
(Ref. FSM 7151.4)Tract or  
Survey No. \_\_\_\_\_  
Cor. No. R-6T 1 S R. 36 E R.D. Pendleton County Umatilla  
Merid. Willamette N.F. Umatilla State Oregon

## CORNER DIAGRAM

## DESCRIBE CORNER MONUMENT FOUND

T 1 S R 36 E  
           S 20  
 W 1/16  
           S 29  
 RPE 2808  
 1976

None

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

## PHOTO IDENTIFICATION DATA

 Photo No. \_\_\_\_\_  
 Filed At. \_\_\_\_\_  
 Object Ident. \_\_\_\_\_  
 Ident. By \_\_\_\_\_  
*Signature* \_\_\_\_\_

## DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Go 1 mile down road to Huron, 400 feet past a steel gate. Corner is 60 feet E of road, in a creek bottom.

## PLANE COORDINATE POSITION DATA

 State \_\_\_\_\_ Zone \_\_\_\_\_  
 X \_\_\_\_\_  
 Y \_\_\_\_\_  
 Estab. By \_\_\_\_\_

 Signature James D. Hauke Title \_\_\_\_\_ Division ORPE 2808 Headquarters \_\_\_\_\_ Date 5-27-76 7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 2½" brass cap on 2" iron pipe 31" long, 6" above ground in earth and rock mound with steel fence post and sign 54-4 alongside.

S 20  
W 1/16  
S 29  
RPE 2808  
1976

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir, 12" diam. bears S 13° W, 16.5 ft. dist., mkd. W 1/16 S 29 BT.

A fir, 6" diam., bears N 20° E, 57.0 ft. dist., mkd. W 1/16 S 20 BT.

BTs have sign 54-3 attached 6" below band of red paint with a brass washer mkd. RPE 2808 nailed flush with BT blaze.

Work Done By Jas. D. Hanley Title Engr. Date 5-27-76 State Registration No. ORPE 2808  
or Agency  
Certified Cor. Record Prepared ? Yes XX No Filed At: Pendleton Date 8/ /76

REMARKS

Found a 5/8-inch diam. rebar S. 58° 14' 24" E., 118.09 ft. from the proportionate corner location described above. There are also two BT at this spurious location. The rebar and BT were not destroyed, this survey.