

USDA-FOREST SERVICE

Index

File No. T-5

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or

Survey No. _____

Cor.

No. _____

T 1S R. 36E

R.D. Pendleton


County Umatilla

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Stone 19"x10"x5" with 1/4 chisled vertically on face on ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

Orig. 24" Pine now charred remains of a large Pine stump N55W-9 lks..

PHOTO IDENTIFICATION DATA

Photo No. 480-206

Filed At. Umatilla N.F.

Object Ident. Three I.P.'s

Ident. By Larry D. Bishop
Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

Signature

Larry D. Bishop

Title

Land Surveyor

Division

Headquarters

Date

10/82

7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½"x30" Gal. steel pipe 26" in ground.

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Larch S70½W, 27.4 ft. scribed ¼S30BT and with a 1" Brass disk stamped PLS 896.
8" D-Fir N74E, 21.2 ft. scribed ¼S29BT and with a 1" Brass disk stamped PLS 896.

Work Done By Larry D. Bishop Title Surveyor Date 10/82 State Registration No. 896
or Agency _____
Certified Cor. Record Prepared? Yes No Filed At: Umatilla County Date Nov. 1982

REMARKS

Set guard post North with sign 54-4 only.
Nailed 54-4 and BT signs to BT's and painted band and blazes red.

Index File No. T. R. M. Tract or Surv. No. Cor.