

USDA-FOREST SERVICE

Index
File No. T-9

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or
Survey No. _____
Cor.
No. _____


T 1S R. 36E

R.D. Pendleton County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

2 1/2" Gal. steel pipe with a 2 1/2" Brass cap properly stamped and firmly set in a mound of stone.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

RPE 2808 12" now 12" Larch N82W, 19.1 ft. scribing visible on partially healed double blaze.
RPE 2808 9" Fir now 9" x 3' tall Pine stub N53E, 15.2 ft. scribing visible on unhealed lower blaze.

PHOTO IDENTIFICATION DATA

Photo No. 480-207
Filed At. Umatilla N.F.
Object Ident. Two I.P.'s
Ident. By Larry D. Brubay
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From its junction with Road #31 follow Rd.#3102 North 0.6 mile. Corner is 300 ft. East.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____
Agency

Larry D. Brubay
Signature

Title Land Surveyor Division _____ Headquarters _____

Date 10/82 7100-52-(3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Larch S58E, 20.0 ft. scribed $\frac{1}{4}$ S28BT and with
a 1" Brass disk stamped PLS 896.

Work Done By Larry D. Bishop Title Surveyor Date 10/82 State Registration No. 896
or Agency

Certified Cor. Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Set guard post North and West with sign 54-2 and 54-4.
Replaced attention sign on Larch BT with sign 54-4.
Nailed BT and 54-4 sign to new BT and painted band and blaze red.

Index File No. T. R. M. Tract or Surv. No. Cor. 12 13

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Index
File No. T-9

Tract or Survey No. _____
Cor. No. T-9

T 1 S R. 36 E WM R.D. Pendleton County Umatilla
Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____
Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Rock Spring Road for 0.7 miles from junction with Mt. Emily Road and turn right on small spur to North boundary of thinning area. Go East on North bdry. 260 feet.

PLANE COORDINATE POSITION DATA

State _____ Zone _____
X _____
Y _____
Estab. By _____

James H. Fowler
Signature _____
Agency _____

Title ORPE 2808

Division _____

Headquarters _____

Date 10-22-75

7100-52 (3/68)

6

7

8

2

3

4

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

T 1 S R 36 E

Set 2½ " brass cap on 2" iron pipe, 31 " long,
6 " above ground with 6 ft. steel fence post
alongside in earth and stone mound. 54-4 and
54-2 signs attached to fc. post.

S 29 ¼ S 28

**RPE 2808
1976**

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

12" larch bears N 82° W, 19.1 ft. dist., mkd. ¼ S 29 BT.

9" fir bears N 53° E., 15.2 ft. dist., mkd. ¼ S 28 BT.

BTs have sign 54-3 attached 6 " below band of red paint
and a brass washer mkd. RPE 2808 nailed flush with BT blaze.

10

Work Done By Jas. D. Hanley Title Engr. Date 5-20-76 State Registration No. ORPE 2808
or Agency

Certified Cor. Record Prepared ? Yes Filed At: Pendleton, Oregon Date 8-2-76

11

REMARKS

¼ corner is at NE corner of thinning boundary.

12