


V-11

History of original corner establishment:

Corner monumented in 1882 by Herman D. Gradon under contract No. 452, Set a stone 12"X10"X5", 8" in the ground, marked 1/4 on North face, Pine, 20" diam., N.65°W., 30 links, marked 1/4 SBT, Tamarack, 20" diam., S.45°E., 18 links, marked 1/4 SBT. Note: No restoration notes appear in county records.



V-11

Description of corner evidence found:

Stone 12"X10"X5" laying on its side with scribes "1". 20" DBH Ponderosa Pine, N.65°W., 30 links, with unopened face.

C.J. MARTIN SURVEYING
2751 JUNIPER ST.
SWEET HOME, OR 97386

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Clayton J. Martin

OREGON
JULY 18, 1980
CLAYTON-JESSE MARTIN
1910

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" diam brass cap in a 2"X30" iron pipe at the Corner, buried cornerstone alongside pipe.

Cap Stamped T1S R36E
1/4 S28
S33

12" D.B.H. White Fir, S.42°E., 17.0', scribed 1/4 S33BT, set a brass washer marked RPLS 1910 between B&T

RPLS 1910
1982

Both B.T.'s. have B.T. tags, attention signs and red painted bands. Steel fence posts 4.0'+ East and West of Corner with attention, monument and boundary signs attached.

Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 30th day of September, 1982
David K. Mumber by Betty Slatta
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY
Umatilla County Surveyor
Date 9-82
Rec'd by BFS
I.o. 82-109-R