


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

H-161

19

History of original corner establishment: Corner established in Oct. 1882 by Hansen D. Gradon, under General Land Office Contract No. 452.

Surveyor General records (notes) states:
Set a basalt stone 12x10x10 ins. 8 ins in the ground for the cor. to sec. 27, 28, 33 & 34, marked with 1 notch on South and 3 notches on East edges, from which Pine 13 ins. diam. bears N 35° E, 62 lks. dist. marked



V-13

T 1 S, R 36 E, S 27 B.T.

A Tamarack 20 ins. dia. bears S 65° E 15 1/4 lks. dist. marked T 1 S, R 36 E, S 34 B.T.

A Pine 24 ins. diam. bears S 85° W 118 lks. dist. marked T 1 S, R 36 E, S 33 B.T.


A Pine 9 ins diam. bears N 30° W 32 lks. dist. marked T 1 S, R 36 E, S 28 B.T. note: No restoration appears in the county records

Description of corner evidence found:

- Found a 12"x 10"x10" basalt stone, loos in a mound of stone with marks faintly visible.
- Found a 22 ins. tamarack snag with all scribing visible, bearing S65°E 102.0 ft. dist from the corner position.
- Found a 24 ins. Pine with all scribing visible, bearing N35°E 41.0 ft. dist. from the corner position.
- Found a 30 ins. Pine with scribing visible bearing S85°W 76.0 ft. dist. from the corner position.
- Found a 24 ins. Pine with scribing visible, bearing N30°W 21.2 ft. dist. from the corner position.

Description of monument and accessories established to perpetuate the original location of this corner

- Set a 30"x2 1/2" iron pipe with 3" brass cap marked as shown, 20 ins. in the ground to solid rock & placed the original stone South & alongside the pipe, & raised a mound of stone around the pipe, for the cor. to Secs. 28, 27, 33 & 34 From which a new Bearing Tree.
- A Lodge Pole Pine 12 ins. diam. bears S61°E 103.6 ft. dist. Marked, T1S R36E S34 BT
- Distance taken to a brass washer in the blaze of the new bearing tree.
- Set a steel fence post approx. 5 ft. west from corner with a Forest Boundary sign attached.



Used a steel tape & magnetic compass with declination equal 20° East.

Office of S. Swinford County of Washtenaw
State of Michigan, I hereby certify that the within instrument was filed in this office for record on the 15 day of March, 1972, at 10 o'clock am, (signed)
Ralph C. Thompson by _____ (DEPUTY)

H-161