


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
 Corner established in Oct. 1882 by Herman D. Graddon,  
 under General Land Office Contract No. 452.  
 Surveyor General records (notes) states:  
 Set a post 4 ft. long 4 ins. square, 24 ins. in the  
 ground for the cor. to secs. 29, 30, 31, and 32  
 marked T 1 S S 29 on N.E.  
 R 36 E S 32 on S.E.  
 S 31 on S.W. and  
 S 30 on N.W. faces with 1 notch in South and 5 notches on East  
 edges from which a fir 12 ins. dia. bears N 30° E 44 lks. dist.  
 marked T 1 S. R 36 E. S. 29 B.T.  
 A Fir 14 ins. dia. bears S. 20° E. 25 lks. dist., marked T 1 S R 36 E.  
 S. 32 B.T. A Tamarack 24 ins. dia. bears S. 35° W. 41 lks.  
 dist. marked T 1 S R 36 E. S. 31 B.T. A Fir 8 ins. dia. bears N.  
 70° W. 22 lks. dist. marked T 1 S R 36 E. S. 30 B.T.  
 Description of corner evidence found:




✓5

Found 30" fir with blaze closed, bearing S20°E 16.5 ft. dist form  
 corner position.  
 Found down & rotten tamarack with blaze face visible, rotten  
 stump bearing S35°W 27.0 ft. dist. form the corner position.  
 Found rotten fir stump with original ax marks visible, bearing  
 N70°W, 15.2 ft. dist. from the corner position.  
 Found original line blazes East & West.

Description of monument and accessories established to perpetuate the  
original location of this corner

Set 30"x24" iron pipe with 3" brass cap marked as shown 24"  
 in the ground, for the corner to sections 29, 30, 31 & 32, form  
 the evidence shown above and raised a mound of stone around the  
 pipe.

From which new Bearing Trees  
 A fir, 14ins. diam., bears N37°E, 21.5ft. dist. marked  
 T1S R36E S29 BT  
 A fir, 8ins. diam., bears S7°E, 25.2 ft. dist. marked  
 T1S R36E S32 BT  
 A fir 12ins. diam., bears S44°W 22.5 ft. dist. marked  
 T1S R36E S31 BT  
 A fir 10ins. diam., bears N43°W 21.7 ft. dist. marked  
 T1S R36E S30 BT



REGISTERED  
 PROFESSIONAL  
 LAND SURVEYOR

OREGON  
 JULY 12, 1968  
 DOUGLAS M. FERGUSON  
 648

All distances taken to a brass washer in the  
 hal-e of each tree.  
 Set a steel fence post approx. 5 ft. west with a  
 attention sign attached.

Used a steel tape & magnetic compass with declination  
 equal 20° East.

Office of Surveyor County of Wasatch  
 State of Utah, I hereby certify that the within Instrument was filed in this office  
 for record on the 17th day of August, 1972, at 11 o'clock am, (signed)  
Ralph D. [Signature] by [Signature] (DEPUTY)