

V-7

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:


Survey was by Herman D. Gradon under contract No. 452, dated June 16, 1882.

Set a post, 3 feet long 3 ins. square, 24 ins. in the ground for 1/4 section corner, from which:

A fir, 8" diam., bears N 15° E., 43 lks. dist., mkd. 1/4 S BT.

A fir, 10" diam., bears S 60° W, 60 lks. dist., mkd. 1/4 S BT.

* Post marked 1/4 S on north face.



V-7

Description of corner evidence found:

Found a badly rotten stump and a piece of overgrowth with scribing 1/4 S BT, S 60° W., 39.6 ft. (60 lks.) dist.

Found a badly rotten tree with slightly visible scribing, N 15° E., 28.4 ft. (43 lks.) dist.

Description of monument and accessories established to perpetuate the original location of this corner


Set a 2 1/2 -inch brass cap on a 2-inch iron pipe, 31 inches long, 6 inches above ground in an earth and rock mound with 6 ft. steel fence post alongside and sign 54-4 attached.

A 10" fir bears N. 15° 30' E., 41.8 ft. dist., mkd. 1/4 S 29 BT.

A 12" larch bears S. 69° 30' E., 39.0 ft. dist., mkd. 1/4 S 32 BT.

Placed signs 54-2 on north and east edges of a 8" fir alongside corner monument.

Monument marked:



Office of Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the 26 day of August, 1976.
 _____ by _____
 (COUNTY OFFICIAL) (DEPUTY)



G-12