


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original monument was a 3 1/2 foot post with bearing ties. Arnold Gibson visited this sight in 1969 and found no evidence of post or bearing trees. To perpetuate the monument he set 1 1/2" x 36" galvanized iron pipe with 3" bronze cap marked "Oregon State Board of Forestry 1/4 S31 1969 RS 359", 18 inches in ground, in line with original blazes, in mound of rock at 40 chains north on east boundary of Section 36.

As accessories: A 10" fir bears S10°E, 41.7 ft. to face, marked 1/4 S31 Bt.
A 14" fir bears S14°W, 34.3 ft. to face, marked 1/4 S31 Bt.
A 4" x 4" x 48" white cedar post 2.0 ft. SW of corner.

X-1



Description of corner evidence found:

Found 3" bronze cap on 1 1/2" galvanized iron pipe with 18" protruding above ground marked Oregon State Board of Forestry 1/4 S31 1969 RS 359.

A 4" x 4" white cedar post stands SW 7 ft.±, no evidence of bearing trees.

Description of monument and accessories established to perpetuate the original location of this corner:

New accessories set:

A brass cap, (2") diameter, on a (1 1/4") diameter galvanized iron pipe (30") long bears N 83° W 57.50', with steel post/paddle alongside.

A brass cap (2") diameter, on a (1 1/4") diameter galvanized iron pipe (30") long bears S 22° W, 54.02', with steel post/w paddle alongside.

A 5/8" iron rod with aluminum cap stamped OSHD bears N 22° E, 168.60 ft. with steel post alongside.

A 5/8" iron rod with OSHD aluminum cap bears S 83° E 196.49' with steel post alongside.

Distances measured with DI 1600, bearings established with Silva compass at 20° dec.

I hereby certify that these references were established on May 12, 1995.

RECEIVED BY
Umatilla County Surveyor
Date 12-96
Rec'd By RC
No. 96-194-B

Expires 12/31/97
Oregon Dept. of Transportation
3012 Island Avenue
La Grande, OR 97850

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert E. Butler
OREGON
JULY 25, 1995
ROBERT E. BUTLER
2733

Office of County of

State of I hereby certify that the within instrument was filed in this office for record on the

..... day of, 19.....

..... by
(County Official) (Deputy)

X-1