

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner originally established by Jacob C. Cooper under GLO contract number 397, dated July 1, 1881. Surveyor General record states:

Set post 3 1/2 ft long 3 ins square 18 ins in the ground on the S hillside 150 ft above bottom of ravine in open timber for 1/4 sec. cor. marked 1/4 S on E and W faces from which;

A pine 18 ins diam bears S89°W 10 lks dist marked 1/4 S BT
No other trees in limits and raised a mound of stone alongside.

Range line resurveyed by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:
As the corners on the West boundary of this Township are not suitable for survey of T1S R37E. . . I am therefore compelled to resurvey it. 48.57 ch-The 1/4 sec corner.
(Meldrum did not destroy any marks or accessories as there were none referring to R37E)



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found no evidence of the original corner monument.

Found a 24 inch diameter Ponderosa Pine S89°W, 10 lks, live and vigorous with blaze evident.

Distance to the original bearing tree is to the estimated face of blaze.

Description of monument and accessories established to perpetuate the

original location of this corner: At record bearing and distance from the above described original bearing tree, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 27 inches in the ground, from which:

New Bearing Tree:

A 9 inch diameter Ponderosa Pine bears N16°W, 22.57 feet marked 1/4 S36 BT

Raised a small mound of stone around monument.

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet South with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on September 20, 1989.

Witness: Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of The Survey Dept County of Umatilla
State of OR I hereby certify that the within instrument was filed in this office
for record on the 27th day of October 1989
David A. Kumbier by Kathleen A. Ambsberg
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

*GPO-591-971, 1988

RECEIVED BY
DATE 10-29
BY KA
NO. 89-101-B