

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

Corner originally established by Henry Meldrum under GLO Contract No. 450, dated June 11, 1882. Surveyor General record states: Set post 4 ft long 4 in square, 24 in in ground for Cor to Secs 6 & 7, marked

T.1S. R 37 E on E
S 6 on N and
S 7 on S faces, with
5 notches on S and

1 notch on N edges, from which:

- A pine 12 in diam bears N 72° E 47 lks dist marked T.1.S. S 6. BT.
- A pine 10 in diam bears S 58° E 14 lks dist marked R.37.E. S 7. BT.
- A fir 6 in diam bears N 73° W 24 lks dist marked R.36.E. BT.



Description of corner evidence found:

No remains of original corner found, re-established by single proportionate measurement, using U.S. Deputy Surveyor, Henry Meldrum's record, from GLO contract no. 450.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" aluminum cap on 2½" x 30" aluminum pipe - 25" in the ground with mound of earth to cap, marked as shown in corner diagram. Set steel fence post with signs 54-2 and 54-9 attached - 2.6 feet South of monument.

From which:

- A 5/8" x 30" iron pin with yellow plastic cap bears N 44° E - 23.3 feet.
 - A 5/8" x 30" iron pin with yellow plastic cap bears N 84 3/4° E - 15.9 feet.
 - A 5/8" x 30" iron pin with yellow plastic cap bears S 68° E - 34.1 feet.
 - A 5/8" x 30" iron pin with yellow plastic cap bears S 34° E - 23.4 feet.
- Attached sign 54-3 to iron pins, and sign 54-9 to steel fence posts set near iron pins.

I hereby certify that the above corner was properly monumented to U.S.F.S. standards by me on November 3, 1994.

Compass declination 18° East.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

renews 12-31-94

Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 3 day of December, 1994
David H. Kline by _____
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 12-94
 Rec'd By KK
 No. 94-170-B