


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO contract number 450, dated June 11, 1882. Surveyor General record states:

Set post 3 ft long 3 in square 24 in in ground for 1/4 sec cor marked 1/4 S on N face from which;

A fir 10 in diam bears N62°W 30 lks dist marked 1/4 S BT
A tamarack 24 in diam bears S20°W 14 lks dist marked 1/4 S BT



No record of subsequent monumentation found in Umatilla County survey records.

Description of corner evidence found:

Found the rotted remains of the original corner post to a depth of 8 inches.

ORIGINAL BEARING TREE

Found a 21 inch diameter Western Larch S20°W, 14 lks dead and standing with scribes visible.

Found no evidence of the original Northwest bearing tree.

Distance to the original BT is to the estimated face of blaze.

Description of monument and accessories I established to perpetuate the

original location of this corner: In place of the found original corner post, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 30 inches in the ground, from which:

New Bearing Trees:

A 8 inch diameter Western Larch bears N1°E, 36.10 feet marked 1/4 S6 BT
A 5 inch diameter Spruce bears S41°E, 77.51 feet marked 1/4 S7 BT

Painted a 6 inch red band around all BTs and attached bearing tree and land survey monument signs.

Set a steel fencepost approximately 5 feet North with land survey monument sign attached.

I hereby certify that the above corner point was perpetuated as hereon described on August 4, 1989.

Witnesses: Jeff Petersen and Rick Robinson



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of the Survey Dept. County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 27th day of October 1989
David H. Kumberson by Kathleen K. Amosberg
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY

*GPO-591-971, 1988

Umatilla County Surveyor

10-89
 KA
 No. 89-106-R