


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

G-1

History of original corner establishment:

None. Corner established as part of this survey, by section subdivision. Corner was established at the midpoint between the Northwest and Southwest corners of Section 7 and on East line of Section 12 (senior line).



Description of corner evidence found:

None.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe, 25" in the ground, with a mound of earth to cap, marked as shown in corner diagram. Set steel fence post with 54-2 and 54-9 signs attached, 1.7 feet South of monument.

From which:

A 23" pine bears N 56° E - 58.2 feet, scribed: 1/4 S7 BT.
An 11" douglas fir bears S 63 1/4° E - 48.7 feet, scribed: 1/4 S7 BT.
A 22" white fir bears S 31 1/2° E - 38.3 feet, scribed: 1/4 S7 BT.
A 21" white fir bears S 11° E - 76.6 feet, scribed: 1/4 S7 BT.
New bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached 54-3 and 54-9 signs, painted 6" red band and face of blaze red.

I hereby certify that the above corner monument was properly monumented to U.S.F.S. standards by me on November 3, 1994.

Compass declination 18° East.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

renews 12-31-94

Office of Surveyor County of Umatilla
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the 27 day of December, 1994
David H. Kelly by _____
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 12-94
Rec'd By AA
No. 94-170-B