


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by Henry Meldrum under GLO Contract No. 450, dated June 11, 1882. Surveyor General record states: Set basalt stone 18 x 9 x 7 in in ground for Cor to Secs 7 & 18, marked with 4 notches on S and 2 on N edges, and raised a mound of stone alongside. Pits impracticable, from which: A pine 24 in diam bears S12°E 39 lks dist marked T.1S. R.37E. S.18 B.T.



Description of corner evidence found:

Nothing found of original corner or bearing tree. Re-established corner by single proportionate measurement, using U.S. Deputy Surveyor, Henry Meldrum's record.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set a 2½" aluminum cap on 2½" x 30" aluminum pipe, 20" in the ground, with a mound of stone to cap, marked as shown in corner diagram. Set steel fence post with 54-2 and 54-9 signs 1.7 feet North of monument From which:
 A 12" douglas fir bears N 29° E - 40.1 feet, scribed: T1S R37E S7 BT.
 A 15" douglas fir bears N 46½° E - 62.2 feet, scribed: T1S R37E S7 BT.
 A 16" douglas fir bears S 31° E - 32.1 feet, scribed: T1S R37E S18 BT.
 A 13" ponderosa pine bears S 12½° E - 71.3 feet, scribed: T1S R37E S18 BT.
 Bearing trees have a brass washer stamped 'PLS 1106' nailed to the face of the blaze. Attached 54-3 and 54-9 signs, painted face of blaze red and 6" red band around each bearing tree.

I hereby certify that the above corner was properly monumented to U.S.F.S. standards by me on September 30, 1994.

Compass declination 18° East.

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

William R. Wells

OREGON
 JULY 22, 1977
 WILLIAM R. WELLS
 1106

renews 12-31-94

Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 2 day of December, 1994
David H. Wilson by _____ (DEPUTY)
 (COUNTY OFFICIAL)

Form R6-7100-57 (9/71)

RECEIVED BY

Umatilla County Surveyor

Date 12-94

Rec'd By KK

No. 94-170-B

*GPO-591-971, 1988